



# ATLAS SCT Status

1. SCT Overview
2. Silicon Sensors
3. ASIC's
4. Modules
5. Optical Links
6. Power Supplies & Cables
7. System Test

## SCT System Overview



### ATLAS Semiconductor Tracker

- ◆ barrel - 4 barrels
    - 2112 modules
  - ◆ forward - 2 × 9 disks
    - 1976 modules
- of 2 × 2 detectors  
glued back-to-back  
at small stereo angle

...or broken up

- ◆ 15392 detectors
  - 63 m<sup>2</sup> active Si
- ◆ 49056 ABCD ASIC's
  - 6.3 M channels

... and also

- ◆ 500 km of cables
  - 30 kW of power in
- ◆ heat exchangers, pipes
  - 30 kW of power out
- ◆ 1500 km of optical fibres
  - control & read out



## Silicon Strip Sensors

- 👉 PRR in August 2000 after 5 % preseries qualification
- ✍ series sensor production underway (January 2001 - end 2002) at Hamamatsu (> 80 %) and CIS
- ✍ 1 barrel (~ square) and 5 forward (wedge) detector types
- 👉 insertable pixel layout required change of inner disk (W12) detectors




## Silicon Strip Sensors (cont.)

16 % of barrel and 16 % of forward detectors delivered

👉 acceptance QA currently at 8 SCT institutes

- ❖ every detector
  - visual inspection
  - I-V to 500 V
- ❖ 10 % subsample
  - depletion voltage
  - full strip evaluation
  - metal  $R$
- $C_{interstrip}$

👉 current average yield of perfect strips - 99.9 % 🟢



UNIVERSITY OF CAMBRIDGE

ATLAS Production Testing Status at Cambridge

Detector: 2022000200001

Delivered batches: 04MAY2001\_120B2

Test Summary for batch 04MAY2001\_120B2:

```

ERROR: file 10 # of detectors delivered in this batch: 120
# re-allocated for QA testing: 0
# tested locally: 120
# completed all compulsory tests so far: 46
# of these which passed without problem: 43
# detectors flagged as FAILED: 0
# with compulsory tests still pending: 74

Test statistics so far:
Visual Inspection: 45 = 38.3 %
StripTest: 47 = 39.1 %
Vmap: 7 = 5.8 %
Current Stability: 0 = 0.0 %
Coupling Capacitance: 0 = 0.0 %
Series Resistance: 0 = 0.0 %
Spoly: 0 = 0.0 %
Interstrip Capacitance: 1 = 0.8 %


Tests FAILED:
> None
    
```

[Back to HEP Introduction](#)



## Silicon Strip Sensors (cont.)

- ☞ **irradiation tests** (to  $3 \times 10^{14}$  p/cm<sup>2</sup>) - full detectors, miniature detectors
- ◆ I-V < 0.25 mA up to 450 V @ -18°C
- ◆ CCE 90 % @ 350 V (40 MHz SCT128A)



## ASIC's



- 👉 frame contract with ATMEL in place
- 👉 minimum guaranteed yield **26 %** (upper limit on cost)
- 👉 target yield **38 %**
- 👉 so far all delivered wafers (well) **below or at minimum yield** 📌
- 👉 (at least) a big load on testing
- 👉 ATMEL believe **target yield can be met** with new epitaxial material and defect screen in place prior to metal deposition
- 👉 new test set-up developed at LBNL installed and being qualified at CERN, LBNL, RAL and UCSC wafers already tested with old CERN tester serve as benchmark
- ✓ testers operational but improved test algorithms need to be completed for full production

## ASIC's (cont.)



ABCD3T **irradiation** with PS protons to  $3 \times 10^{14}$  **cm<sup>-2</sup>** in Oct/Nov 00  
👉 two problems experienced

- ❖ receiver circuit: **higher  $V_{dd}$**  (up to 4.8 V) needed for operation
  - 👉 not understood completely
  - 🍃 appears beyond  $2 \times 10^{14}$  p/cm<sup>2</sup> on some chips from one wafer
  - ✓ not seen in recent irradiation on  $4 \times 12$  ABCD3T chips
- ❖ trimming circuit: **problem** of trim-DAC range setting
  - 👉 understood in simulation
  - ✓ solved by metal mask modification and reprocessing
  - ✓ not appearing in recent irradiation

👉 PRR scheduled July 4<sup>th</sup>



## Modules - Barrel

procurement/production starting



- 👉 FDR passed May 24,25
  - ✍️ module shown to adhere to ATLAS SCT specs
- selected performance figures from FDR:
- ❖ pre-irradiation noise summary (1400-1700 e<sub>0</sub>)
  - ❖ noise occupancy vs. threshold
    - **stable operation** to zero threshold
    - occupancy **1.3 × 10<sup>-5</sup>** @ 1 fC threshold
  - ❖ signal/noise of unirradiated (**15** > 200 V) & irradiated (**10** @ 400 V) modules in KEK beam
  - ❖ resolution from CERN H8 Aug'00 - **23 μm**
  - 👉 3 modules **irradiated** in April 2001 - under annealing & evaluation
  - ✍️ pre-series production of 18 module-0 ongoing, stock building up
  - 👉 production starting **November 01**, completed **June 03** in 4 clusters: **Japan, Nordic, UK, US**



## Modules - Endcap





- 👉 a few months behind barrel
- ✅ new hybrid K4 - carbon-carbon substrate - improved thermal performance



# Modules - Endcap (cont.)



- first pre-series modules under test, **stability problems**
- to great extent solved  $\Rightarrow$  **irradiation** of one module at CERN PS now




- to start production in **February 02** requires **FDR** in **July**
- difficult to meet, decision at SCT week end June

# Optical links




new collaborator: Academia Sinica, Taiwan:

- ◆ Trueilight PIN/VECSEL packages replacing GEC
- ◆ electro-optical harness assembly



## Optical links (cont.)

harness assembly tests at RAL:  
✓ first harnesses produced and tested



## Optical links (cont.)



DORICs and VDCs production wafers back  
✍ first wafer tested, yield 95 %

### Schedule:

- ✍ opto-ASIC (DORIC, VDC) FDR in July 01
- ✍ opto-electrical harness FDR September 01
- ⇒ harness production: September 01 → January 03

## Power Supplies and Cables



👉 **doubled power** requirements  $\Rightarrow$  increased cost & volume required for services ❗

👉 PS critical design review, EB gap task force

$\Rightarrow$  two important and helpful concessions by ATLAS

- ❖ PP2 in muons at  $z \sim \pm 3.5$  m
- ❖ 40 mm gap enlargement in  $z$


... working hard to fit services in allocated space considering all possibilities



# Power Supplies and Cables (cont.)

- baseline **just fits**, but not fully modeled
- technology to be finalized on basis of **reliability, cost & space**

## SCT Power distribution baseline scheme





## Power Supplies and Cables (cont.)

options considered (under **severe schedule pressure**)

- ❖ (ultra-)thin TP cables to PP1 (fit in ID space ?)
- ❖ modularity & packing of services (module noise ? space gain ?)
- ❖ modularity of power supplies (module noise ? cost gain ?)
- ❖ move power supplies to UX-15 (radiation tolerance ? SEU ?)

 **deadline** imposed by **assembly schedule**: Power Supply FDR/PRR March 02

 low-mass cables included in opto-electrical harness FDR September 01

currently

-  ~ 100 LV power supplies in production for system-test / assembly site needs
-  production of low-mass tapes for system test and harness prototype assembly




## System Test



purpose:


- ◆ test multiple modules in a realistic SCT environment, including SCT PS & cables/harnesses and opto readout
- ◆ find optimal grounding & shielding scheme



## System Test - Barrel




barrel - 10 modules on sector (3+1 half-staves)  
equipped with cooling pipe & opto-electrical harnesses (3 LH + 1 RH)



## System Test - Barrel (cont.)



- grounding & shielding scheme for barrel
- ◆ jumpers on patch panels allow easy configuration changes
  - ◆ a lot of “Scotch physics” still going on





# System Test - Barrel (cont.)



selected results



✓ modules behave almost as well on the sector as on electrical stand



## System Test - Barrel (cont.)



- some fluctuations in noise seen on chips close to neighboring module
- fluctuations significantly decreased when grounding and shielding improved



looks promising


- but 10 is still a very small number of modules
- ... we're still in the early days

## System Test - Endcap



endcap test stand



👉 new modules arriving



# System Test - Endcap (cont.)



- previous results - endcap modules noisier (higher T) & more sensitive to common mode noise
- hope to have improved by new hybrid (lower T) and better grounding & shielding





## System Test - Future Plans

### ✓ barrel plans:

- ◆ add more modules
- ◆ test configurations
  - module completely surrounded by other modules
  - row of 12 modules supplied from both sides coupled to same cooling pipe
- ◆ continue studying & improving grounding & shielding
- ◆ incorporate a ROD
- ◆ incorporate power-supply-0

### ✓ endcap plans:

- ◆ continue work on quantifying & fighting common-mode noise
- ◆ quarter-disk to arrive end of June
  - 33 module positions
  - enough supplies and readout to operate 18 modules simultaneously
  - with sufficient modules, same type program as on barrel now

### ✓ for both barrel and endcap

- ◆ test redundancy scheme for opto readout
- ◆ run at ATLAS temperatures: hardware ready now
- ◆ try interchanging barrel ↔ endcap grounding & shielding schemes





## Conclusions

 **SCT on good track to move into bulk production** 

- ❖ some parts (detectors) already at full steam
- ❖ some (barrel modules) just starting
- ❖ the rest to follow soon

**with a bit of luck and a lot of hard work ...**

... at next overview week SCT will be just giving production status reports 